


Unit Overview - AHU 1-2								
Application	Unit Size	External Dimensions			Weight			
	Utilit Size	Height	Width	Length	Installed	Rigging		
Indoor unit	CSAA017	52.5 in	72.0 in	116.940 in	2220 lb	2102 lb		
Overtity of Chi	Quantity of Shipping Sections		Largest Ship Split			Elevation		
Quantity of Sni			Width	Length	Heaviest Ship Split	Elevation		
2 piece(s)		101.5 in	72.0 in	84.6 in	1822 lb	0.00 ft		

Supply Fan						
Airflow	6700 cfm	<b>Total Static Pressure</b>	3.698 in H2O			

Construction Features					
Panel	2in. foam injected R-13 with thermal break				
Panel Material	All unit inner panels - galvanized				
Integral Base Frame	6in. integral base frame				
Short Circuit Current Rating	65 kA				
Agency Approval	UL listed unit				



Unit Electrical				
Circuit	Voltage/Phase/Frequency	FLA	MCA	Max Fuse Size
Circuit number 1 Supply fan motor(s)	200-208/3/60	23.29 A	26.04	35.00

Unit Acoustics								
Sound Path	63 (Hz)	125	250	500	1K	2K	4K	8K
Supply top:	72 dB	87 dB	82 dB	81 dB	78 dB	77 dB	74 dB	67 dB
Return:	74 dB	81 dB	78 dB	71 dB	70 dB	69 dB	65 dB	57 dB
Casing:	74 dB	83 dB	73 dB	70 dB	69 dB	55 dB	52 dB	47 dB

Unit Controls	
Controller Type	No controller
Warranty	
Warranty soction	Std warranty only



Air mixing section - Position: 1									
Openings									
Face	Path	т Туре	Airflow	Face Velocity	Area	Pressure Drop		Hood	
Тор	Retur	Sizeable rn rectangular opening	6700 cfm	0 cfm 791 ft/min 8.47 sq ft		0.00	0 in H2O	N/A	
			Fil	lter					
Туре		Frame	MERV	Rating	Quantity		Size		
Pleated media -	MERV 13	2"	MER	RV 13	2.00 4.00			Din.x20in. Din.x24in.	
Pressure D	rop	Condition	Face V	/elocity	Airflow		Area		
0.633		Mid-life	355	ft/min	6700 cfm		18	8.89 sq ft	
			Section	Options					
Door Location Right									

Heating coil section - Position: 2							
Coil Con	struction	Coil Performance					
Model	Hot water - 5/8" Shipping Coil, General (5W)	Сара	acity				
Rows		Total	159.91 MBh				
	5/8in. tube diameter (15.875 mm)	A	ir				
Coil Connection	` ,	Flow	6700 cfm				
Tube Matl/Wall Thickness	.020" (0.508 mm) copper tubes	Entering Dry Bulb	34.00 F				
Fin Spacing	80 Per Foot	Leaving Dry Bulb	56.01 F				
Fin Material	Aluminum fins	Pressure Drop					
Fin Type	Prima flo E (energy efficient)	Face Velocity	447 ft/min				
Face Area	Face Area 15.00 sq ft		uid				
Coil (top/single) H x L	36 in. (914 mm) X 60" (1524 mm) finned length	Flow	16.02 gpm				
Casing	Stainless steel	Entering					
	CompleteCoat(TM) Epoxy E-coat		120.00 F				
Turbulators	Not Included	Pressure Drop					
Rigging Weight	69.7 lb	Tube Velocity					
Installed Weight		Reynolds Number					
Coil Section	on Options	,,	Water				
			0.00025 hr-sq ft-deg F/Btu				
Extended Drain and Vent	•	Volume	2.67 gal				
Drain Pan Size		AHRI 410 CI	lassification				
Door Location	Rigiti	AHRI 410 Classification	NOT Certified by AHRI				
		Data Generation Date	7/10/2024				
		Trane Select Assist update number	2840				

Note: Coil is NOT certified by AHRI. Coil is within the scope of AHRI Standard 410.



Cooling coil section - Posit	ion: 3			
Coil Con	struction	Coil Performance		
Model	Chilled water - 1/2" Unit Optimized, General (UW)	Capacity		
Rows		Total	374.32 MBh	
	1/2in. tube diameter (12.7 mm)	Sensible	226.40 MBh	
Coil Connection	,	A	ir	
Tube Matl/Wall Thickness	.016" (0.406 mm) copper tubes	Flow	6700 cfm	
Fin Spacing	118 Per Foot	Entering Dry Bulb	82.57 F	
Fin Material	Aluminum fins	Entering Wet Bulb	69.81 F	
Fin Type	Delta flo H (Hi efficient)	Leaving Dry Bulb	52.00 F	
Face Area	16.81 sq ft	Leaving Wet Bulb	51.90 F	
Coil (top/single) H x L	40 in. (1016 mm) X 61" (1549 mm)	Pressure Drop	0.842 in H2O	
1 1 2 1	finned length	Face Velocity	399 ft/min	
	Stainless steel	Fluid		
•	CompleteCoat(TM) Epoxy E-coat	Flow	53.28 gpm	
Turbulators		Entering	OI .	
Rigging Weight		Leaving	56.00 F	
Installed Weight		Pressure Drop	12.60 ft fluid	
	on Options	Tube Velocity	2.95 ft/s	
Extended Drain and Vent	•	Reynolds Number	8481.19	
	Stainless steel	Туре	Water	
Drain Pan Size		Fouling Factor	0.00000 hr-sq ft-deg F/Btu	
Drain Connection	0	Volume	11.49 gal	
Minimum Trap Height (L)		AHRI 410 CI	lassification	
H Trap Dimension		AHRI 410 Classification	NOT Certified by AHRI	
J Trap Dimension		Data Generation Date	•	
Door Location	Right	Trane Select Assist update number	2940	

Note: Coil is NOT certified by AHRI. Coil is within the scope of AHRI Standard 410.

Supply fan section - Position: 4							
Fan	Data	Motor Data					
Wheel Diameter/Type/Class	17.7 impeller fan full width	Voltage	200-208/3				
Fan Quantity	2	Impeller Fan Control Voltage	8.5 V				
Discharge Location	Top front	Impeller Fan HP per fan	6.030 hp				
Motor Location	Right side drive	FEI	1.48				
Drive Service Factor	Direct drive	Wire to air static efficiency	62.27 %				
Fan K-factor	Fan K-factor 2229.00		Note: Certified airflow performance per AHRI 430				
Fan Perf	ormance	Fan Section Options					
Airflow	6700 cfm	Backdraft Dampers	Field provided or blockoff plate				
Total Static Pressure	3.698 in H2O	Door Location	Right				
Operating Speed	1918 rpm	Door Guard	Yes				
Fan electrical power (FEP)	4.67 kW	One Fa	n Down				
Max Total Static Pressure @ 10V	5.144 in H2O	Redundancy					
Motor Interf	ace Options	Impeller Fan Control Voltage					
Selection Type	MICP with H-O-A	Operating Speed					
	200-208/3	Operating Speed	2202 Ipili				
Mounting Location							

Fan Discharge Options									
Face	Туре	Airflow	Face Velocity	Area	Pressure Drop	Exhaust Hood	Damper Torque Requirement		
Top Face Feature	Sizeable rectangular opening	6700 cfm	1134 ft/min	5.91 sq ft	0.161 in H2O	N/A	N/A		

Note: Certified by the AHRI Central Station Air-Handling Unit (AHU) Certification Program, based on AHRI Standard 430/431. AHRI certified units are subject to rigorous and continuous testing, have performance ratings independently measured and are third party verified. Certified units may be found in the AHRI Directory at www.ahridirectory.org.






Supply fan Acoustics									
Sound Path	63 (Hz)	125	250	500	1K	2K	4K	8K	
Supply top:	72 dB	87 dB	82 dB	81 dB	78 dB	77 dB	74 dB	67 dB	
Return:	74 dB	81 dB	78 dB	71 dB	70 dB	69 dB	65 dB	57 dB	
Casing:	74 dB	83 dB	73 dB	70 dB	69 dB	55 dB	52 dB	47 dB	

Pressure Drop in (in w.g.)	Pressure Drop in (in w.g.)			
Supply fan				
Air mixing section	0.63			
Coil section	0.06			
Coil section	0.84			
Fan section	0.16			
Internal Static Pressure	1.70			
External Static Pressure	2.00			
Total Static Pressure	3.70			





- 1 count=45
- 2 Opening top 37 x 23
- Plenum fan 17.7 impeller fan full width Supply fan Motorized impeller fan 200-208/3
- Cooling coil 6 Rows
  Coil type 1/2" Unit
  Optimized, General (UW)
- 5 Heating coil 1 Rows Coil type 5/8" Shipping Coil, General (5W)
- 6 Opening top 61 x 20

Doors 20 width x 42 height 22 width x 42 height

27 width x 42 height

For maneuvering purposes, include 1.125 inches to each ship split length for overlapping panel flange. Flange will not add to overall installed unit length shown.


#### OPENING AND DIMENSIONS MAY VARY FROM CONTRACT DOCUMENTS / RETURN OF APPROVED DRAWINGS CONSTITUTES ACCEPTANCE OF THESE VARIANCES / NOT TO SCALE

			_
Unit size: 17	Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Product group: Indoor unit	6700 cfm	Proposal Number:	
Integral base frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	-
Paint:		2101.6 lb / 2219.9 lb	



**TRANE**° Performan





- 1 count=45
- 2 Opening top 37 x 23
- Plenum fan 17.7 impeller fan full width Supply fan Motorized impeller fan 200-208/3
- Cooling coil 6 Rows
  Coil type 1/2" Unit
  Optimized, General (UW)
- 5 Heating coil 1 Rows Coil type 5/8" Shipping Coil, General (5W)
- 6 Opening top 61 x 20
- 7 3/8"
- 8 1" N.P.T.E

Doors

20 width x 42 height

22 width x 42 height 27 width x 42 height

For maneuvering purposes, include 1.125 inches to each ship split length for overlapping panel flange. Flange will not add to overall installed unit length shown.


OPENING AND DIMENSIONS MAY VARY FROM CONTRACT DOCUMENTS / RETURN OF APPROVED DRAWINGS CONSTITUTES ACCEPTANCE OF THESE VARIANCES / NOT TO SCALE

Unit size: 17	Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Product group: Indoor unit	6700 cfm	Proposal Number:	1
Integral base frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	] '
Paint:		2101.6 lb / 2219.9 lb	




**TRANE**° Performance Cl





#### For maneuvering purposes, include 1.125 inches to each ship split length for overlapping panel flange. Flange will not add to overall installed unit length sh

Pos#	Module	Length	Weight
1	Air mixing section	32 3/8	397.94
2	Coil section	31 3/8	337.28
3	Coil section	53 1/4	885.36
4	Fan section	48	599.32
	Installed U	nit Weigh	t 2219.91 lbs





OPENING AND DIM		NTRACT DOCUMENTS / RETURN OF A OF THESE VARIANCES / NOT TO SCAL	
I Init size: 17	Joh Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	

Unit size: 17	Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Product group: Indoor unit	6700 cfm	Proposal Number:	
Integral base frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	
Paint:		2101.6 lb / 2219.9 lb	










#### \*\*Placement of electrical conduit may vary by a tolerance of 8" in any direction.

## OPENING AND DIMENSIONS MAY VARY FROM CONTRACT DOCUMENTS / RETURN OF APPROVED DRAWINGS CONSTITUTES ACCEPTANCE OF THESE VARIANCES / NOT TO SCALE

Unit size: 17	Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Product group: Indoor unit	6700 cfm	Proposal Number:	
Integral base frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	
Paint:		2101.6 lb / 2219.9 lb	









# OPENING AND DIMENSIONS MAY VARY FROM CONTRACT DOCUMENTS / RETURN OF APPROVED DRAWINGS CONSTITUTES ACCEPTANCE OF THESE VARIANCES / NOT TO SCALE


Unit size: 17	Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Product group: Indoor unit	6700 cfm	Proposal Number:	
Integral base frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	•
Paint:		2101.6 lb / 2219.9 lb	




Performance Climate Changer

Air Handlers





Detailed Elevation View: Front - Measurements in inches



Detailed Elevation View: Back - Measurements in inches

# OPENING AND DIMENSIONS MAY VARY FROM CONTRACT DOCUMENTS / RETURN OF APPROVED DRAWINGS CONSTITUTES ACCEPTANCE OF THESE VARIANCES / NOT TO SCALE


Unit size: 17	Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Product group: Indoor unit	6700 cfm	Proposal Number:	
Integral base frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	
Paint:		2101.6 lb / 2219.9 lb	



Performance Climate Changer

Air Handlers






NPTI : National Pipe Thread Internal Connection NPTE : National Pipe Thread External Connection

#### OPENING AND DIMENSIONS MAY VARY FROM CONTRACT DOCUMENTS / RETURN OF APPROVED DRAWINGS CONSTITUTES ACCEPTANCE OF THESE VARIANCES / NOT TO SCALE

Unit size: 17		Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Product grou	ıp: Indoor unit	6700 cfm	Proposal Number:	
Integral base	e frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	
Paint:			2101.6 lb / 2219.9 lb	








NPTI : National Pipe Thread Internal Connection NPTE : National Pipe Thread External Connection

#### OPENING AND DIMENSIONS MAY VARY FROM CONTRACT DOCUMENTS / RETURN OF APPROVED DRAWINGS CONSTITUTES ACCEPTANCE OF THESE VARIANCES / NOT TO SCALE

Un	it size: 17	Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Pro	oduct group: Indoor unit	6700 cfm	Proposal Number:	
Inte	egral base frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	É
Pa	int:		2101.6 lb / 2219.9 lb	








#### OPENING AND DIMENSIONS MAY VARY FROM CONTRACT DOCUMENTS / RETURN OF APPROVED DRAWINGS CONSTITUTES ACCEPTANCE OF THESE VARIANCES / NOT TO SCALE

Unit size: 17	Job Name: FSDB Kramer	Unit Casing: 2in Double Wall Foam	
Product group: Indoor unit	6700 cfm	Proposal Number:	4
Integral base frame: 6in. integral base frame	Sales Office:	Tags: AHU 1-2	4
Paint:		2101.6 lb / 2219.9 lb	`








		_					I	_		
120	28	197	129	28	83	64	48	101	N N	194
100	28	170	113	28	22	64	48	101	180	167
80	99	156	105	99	83	64	48	63	179	153
99	52	156	105	52	83	64	48	93	170	153
22	48	141	96	48	83	64	48	22	156	138
50	48	141	96	48	83	64	48	22	156	138
40	48	128	88	48	83	64	48	20	140	125
35	48	115	80	48	75	64	48	99	136	112
30	48	109	92	48	83	64	48	99	118	106
25	48	98	29	48	28	64	48	99	115	92
21	48	92	29	48	58	64	48	09	115	92
17	48	87	A/N	48	83	61	48	61	105	84
14	48	87	ĕ/N	48	83	61	48	58	100	84
12	48	82	N/A	48	81	61	48	54	100	79
10	48	22	A/N	48	75	61	48	51	108	74
8	48	99	A/A	48	63	61	48	48	06	63
9	48	69	N/A	48	29	61	48	48	89	56
4	48	59	N/A	48	59	61	48	48	N/A	N/A
8	48	48	A/N	48	43	61	48	48	N/A	N/A
Component	A (filter)	B (coil, humidifier)	B (staggered coil)	C (UV Lights)	C (TCAC)	D (External Starter VFD, LV box or Overload box)	D (Internal Starter or VFD)	E (fan)	F (Gas Heat Ext Vestible)	F (Gas Heat Int Vestible)


o O	Component	₹	
3		Sizes	
5	i i		
¥	G (Side mount LV box)	36	
94	G (Front mount LV box)	13	
		2	




# **Base Detail**







NOMINAL SIZE (WxHxD)	ACTUAL SIZE (WxHxD)	RATED AIR FLOW (CFM)	INITIAL RESISTANCE (IN. W.G.)	MEDIA AREA (SQUARE FEET)	FILTER UNIT WEIGHT (LBS)
12x24x2	11-3/8 x 23-3/8 x 1-3/4	1000	0.41	10.5	0.9
16x20x2	15-1/2 x 19-1/2 x 1-3/4	1120	0.41	10.9	1.1
16x25x2	15-1/2 x 24-1/2 x 1-3/4	1400	0.41	14.9	1.3
20x20x2	19-1/2 x 19-1/2 x 1-3/4	1400	0.41	14.5	1.3
20x24x2	19-3/8 x 23-3/8 x 1-3/4	1670	0.41	17.4	1.4
20x25x2	19-1/2 x 24-1/2 x 1-3/4	1750	0.41	18.5	1.4
24x24x2	23-3/8 x 23-3/8 x 1-3/4	2000	0.41	21.1	1.6




#### STANDARD CONSTRUCTION

- 1. 100 % Synthetic White Media
- 2. 17.5 Pleats Per Foot
- 3. Expanded Metal Pleat Supports
- 4. Moisture Resistant Beverage Board Frame
- 5. Double Wall Frame

#### NOTES

- 1. MERV 13 per ASHRAE 52.2-2012 Tested at 492 FPM on 24x24x2 Nominal Size
- 2. Final Resistance: 1.0" W.G.
- 3. Rated Velocity: 500 FPM
- 4. Classified per U.L. Standard 900 for Flammibility
- 5. Maximum Operating Temperature: 200 deg. F





#### **GENERAL**

Per ASHRAE 62.1 recommendation, indoor air handling units will be wrapped to protect unit from intransit rain and debris.

Installing contractor is responsible for long term storage in accordance with the Installation, Operation, and Maintenance manual (CLCH-SVX07\*-EN).

Unit shall be UL and C-UL Listed.

Supply fans within the scope of AHRI Standard 430 are "Certified by the AHRI Central Station Air-Handling Unit (AHU) Certification Program, based on AHRI Standard 430/431. AHRI certified units are subject to rigorous and continuous testing, have performance ratings independently measured and are third-party verified. Certified units may be found in the AHRI Directory at www.ahridirectory.org".

Unit sound performance data shall be reported as sound power. Trane, in providing this program and data, does not certify or warrant NC levels. These levels are affected by factors specific to each application and/or installation and therefore unable to be predicted or certified by Trane. Refer to product data for specific fan footnote references.

Refer to product data for AHRI certification status. Propylene glycol and calcium chloride, or mixtures thereof, are outside the scope of AHRI Standard 410 and, therefore, do not require AHRI rating or certification. For coils within the scope of AHRI Standard 410 cooling coil performance is certified in accordance with the AHRI Forced-Circulation Air-Cooling and Air-Heating Coils Certification Program which is based on AHRI Standard 410 within the Range of Standard Rating Conditions listed in Table 1 of the Standard. Certified units may be found in the AHRI Directory at www.ahridirectory.org. Heating performance for heat pump or condenser mode is not certified.

#### **Unit Construction**

All unit panels shall be 2" solid, double-wall construction to facilitate cleaning of unit interior. Unit panels shall be provided with a mid-span, no-through-metal, internal thermal break. Casing thermal performance shall be such that under 55°F supply air temperature and design conditions on the exterior of the unit of 81°F dry bulb and 73°F wet bulb, condensation shall not form on the casing exterior. Casing construction will comply with NFPA 90A.

All exterior and interior indoor AHU panels will be made of galvanized steel.

#### **Unit Paint**

Unit to ship unpainted from factory. If required, unit to be painted by 3rd party finisher, or by painting contractor at job site.

#### Casing Deflection

The casing shall not exceed 0.0042 inch deflection per inch of panel span at 1.00 times design static pressure. Maximum design static shall not exceed +8 inches w.g. in all positive pressure sections and -8 inches w.g. in all negative pressure sections.

#### Floor Construction

The unit floor shall be of sufficient strength to support a 300.0 lb load during maintenance activities and shall deflect no more than 0.0042 inch per inch of panel span.

#### **Unit Base**

Manufacturer to provide a full perimeter integral base frame for either ceiling suspension of units or to support and raise all sections of the unit for proper trapping. Indoor unit base frame will either be bolted construction or welded construction. All outdoor unit base frames shall be welded construction. For indoor units, refer to schedule for base height and construction type. Contractor will be responsible for providing a housekeeping pad when unit base frame is not of sufficient height to properly trap unit. Unit base frames not constructed of galvanized steel shall be chemically cleaned and coated with both a rust-inhibiting primer and finished coat of rust-inhibiting enamel. Unit base height to be included in total height required for proper trap height.

#### Insulation

Panel insulation shall provide a minimum thermal resistance (R) value of 13 ft²-h-ºF/Btu throughout the entire unit. Insulation shall completely fill the panel cavities in all directions so that no voids exist and settling of insulation is prevented.

#### **Drain Pan**

In sections provided with a drain pan, the drain pan shall be designed in accordance with ASHRAE 62.1. To address indoor air quality (IAQ) the drain pan shall be sloped in two planes promoting positive drainage to eliminate stagnant water conditions. Drain pan shall be insulated, and of double wall construction. The outlet shall be the lowest point on the pan, and shall be of sufficient diameter to preclude drain pan overflow under normally expected operating conditions. All drain pans connections shall have a threaded connection, extending a minimum of 2-1/2" beyond the unit base, and shall be made from the same material as the drain pan. Drain pan located under a cooling coil shall be of sufficient size to collect all condensate produced from the coil.

Refer to Product Data for specific information on which sections are supplied with a drain pan, the drain pan material and connection location.

#### **Access Door Construction**

Access doors shall be 2" double wall construction. Interior and exterior door panels shall be of the same construction as the interior and exterior wall panels respectively. All doors shall be provided with a thermal break construction of door panel and door frame. Gasketing shall be provided around the full perimeter of the doors to prevent air leakage. Surface mounted handles shall be provided to allow quick access to the interior of the functional section and to prevent through cabinet penetrations that could likely weaken the casing leakage and thermal performance. Handle hardware shall be designed to prevent unintended closure. Outswing doors shall have easily removable hinges and handles that can be relocated to change the door swing if needed. Door hinges shall be made of stainless steel.

All doors shall be a minimum of 60" high when sufficient height is available or the maximum height allowed by the unit height.

Door handles shall be provided for each latching point of the door necessary to maintain the specified air leakage integrity of the unit. An optional shatterproof window shall be provided in access doors where indicated on the plans. Window shall either be single pane, or thermal dual pane, as defined on schedule. Window shall be capable of withstanding unit operating pressures and shall be safe for viewing UV-C lamps.

Refer to Product Data for specific information on which sections are supplied with an access door, the door location, a single handle and a window.

#### **Lifting Instructions**

The air handling units must be rigged, lifted, and installed in strict accordance with the Installation, Operation, and Maintenance manual (CLCH-SVX07G-EN). The units are also to be installed in strict accordance with the specifications. Units may be shipped fully assembled or disassembled to the minimum functional section size in accordance with shipping and job site requirements.

Indoor units shall be shipped on an integral base frame (variable from the standard 2.5" to 8" height) for the purpose of mounting units to a housekeeping pad and providing additional height to properly trap condensate from the unit. The integral base frame may be used for ceiling suspension, external isolation, or as a housekeeping pad. Indoor sizes 3 to 30 will also be shipped with a shipping skid designed for forklift transport. Refer to the unit As-Built or Product Data section of the submittal for the base frame height of each unit.

All units will be shipped with an integral base frame designed with the necessary number of lift points for safe installation. All lifting lugs are to be utilized during lift. The lift points will be designed to accept standard rigging devices and be removable after installation.

#### MIXING SECTION

A mixing section shall be provided to support the damper assembly for outdoor, return, and/or exhaust air.

#### Title 24

The following specifications apply only to units with outside air and return air dampers, with actuators. The 5 year warranty applies only to these items.

This unit contains Economizer that meets or exceeds all mandatory requirements prescribed by Title 24, including but not limited to:

- 5 yr parts only warranty
- Successfully tested to 60,000 Actuations
- Less than 10 cfm/sq.ft. of damper leakage at 1" WG per AMCA 500L

#### **Filters**

Mixing sections shall be provided with a filter rack as indicated in the Product Data and As-Built sections of the submittal.

2 inch pleated media filters made with 100% synthetic fibers that are continuously laminated to a supported steel wire grid with water repellent adhesive shall be provided. Filters shall be capable of operating up to 625 fpm face velocity without loss of filter efficiency and holding capacity. The filters shall have a MERV 13 rating when tested in accordance with the ANSI/ASHRAE Standard 52.2.

#### COIL SECTION WITH FACTORY INSTALLED COIL

The coil section shall be provided complete with coil and coil holding frame. The coils shall be installed such that headers and return bends are enclosed by unit casings. If two or more cooling coils are stacked in the unit, an intermediate drain pan shall be installed between each coil and be of the same material as the primary drain pan. Like the primary drain pan, the intermediate drain pan shall be designed being of sufficient size to collect all condensation produced from the coil and sloped to promote positive drainage to eliminate stagnant water conditions. The intermediate pan shall begin at the leading face of the water-producing device and be of sufficient length extending downstream to prevent condensate from passing through the air stream of the lower coil. Intermediate drain pan shall include downspouts to direct condensate to the primary drain pan. The outlet shall be located at the lowest point of the pan and shall be sufficient diameter to preclude drain pan overflow under any normally expected operating condition.

#### **Coil with Inspection**

The coil section complete with a double-wall, shall include a removable door downstream of the coil for inspection, cleaning, and maintenance. Interior and exterior door panels shall be of the same construction as the interior and exterior wall panels, respectively. All doors shall be provided with a thermal break construction of door panel and door frame.

Casing penetrations supplied for hydronic drain and vents. Piping contractor shall provide extended piping.

#### Water Coils (UP, WP, UW, UU, UA, 3W, 3U, W, 5W, 5A, WD, 5D, D1, D2, P, or TT)

The coils shall have aluminum fins and seamless copper tubes. Copper fins may be applied to coils with 5/8-inch tubes. Fins shall have collars drawn, belled, and firmly bonded to tubes by mechanical expansion of the tubes. The coil casing may be galvanized or stainless steel. Refer to the Product Data section of the submittal for the coil casing material.

The coils shall be proof-tested to 300 psig and leak-tested under water to 200 psig. Refer to the Product Data section of the submittals for AHRI certirification status.

Coil connections are constructed of cast iron with female connections, steel block with female connections or steel pipe with male connections. Type P or TT coil connections do not extend out of unit casing. All other water coil types have connections that extend out beyond unit casing. Headers on downstream coil bank of staggered coil sections do not extend beyond the unit casing and must be completed by the on-site piping contractor.

Tubes are 1/2" [13 mm] OD 0.016" [0.406 mm] thick copper.

Tubes are 5/8" [16 mm] OD 0.020" [0.508 mm] thick copper.

**Coil Coating** 

Coil shall have a flexible epoxy polymer e-coat uniformly applied to all coil surface areas without material bridging between fins. Coating process shall ensure complete coil encapsulation and a uniform dry film thickness from 0.8 - 1.2 mil on all surface areas including fin edges. Superior hardness characteristics of 2H per ASTM D3363-92A and a cross-hatch adhesion of 4B-5B per ASTM B3359-93. Impact resistance shall be up to 160 in/lb per ASTM D2794-93. Humidity and water immersion resistance shall be up to a minimum 1000 and 260 hours respectively (ASTM D2247-92 and ASTM D870-02). Corrosion durability shall be confirmed through testing to no less than 5,000 hours salt spray per ASTM B117-90 using scribed aluminum test coupons.

#### MOTORIZED IMPELLER FAN SECTION

Direct plenum fans provided with electronically commutated external- rotor motor with integrated control electronics, radial aluminum impeller with backward curved, continuously welded blades.

- 1. Individual Fan Assemblies shall be statically and dynamically balanced in two planes as per DIN / ISO 1940 to balancing grade G 6.3.
- 2. Fan-to-fan interaction can cause a significant increase in individual fan vibration when mounted to the same structure. Fans applied in an array shall be tested as a system and the total fan vibration shall be less that 0.42 (in/s) RMS including all fan-to-fan interaction. This system effect shall be accounted for by the air handler manufacturer. Individual fan vibration performance values shall not be acceptable.
- 3. Fan performance is "Certified by the AHRI Central Station Air-Handling Unit (AHU) Certification Program, based on AHRI Standard 430/431. AHRI certified units are subject to rigorous and continuous testing, have performance ratings independently measured and are third-party verified. Certified units may be found in the AHRI Directory at www.ahridirectory.org". Fan shall be spaced to minimize aerodynamic fan interaction. Minimum center-to-center spacing between fans shall be 1.6 diameter ratio to ensure proper performance.
- 4. Fan wheels shall be constructed of materials that comply with UL 1995/60335 requirements of flame and smoke spread per NFPA 90A. The flame spread index not exceeding 25 and a smoke-developed index not exceeding 50.
- 5. Fan Electrical Power (FEP) rated in accordance with AHRI 430-2020.
- 6. Motor shall contain integrated PID controller and accept a 0-10VDC input signal for variable speed control.
- 7. Motor efficiency class shall comply with IE4
- 8. Fan system manufacturer must stock replacement parts in North America
- 9. Fan array shall be designed and constructed for easy field assembly and maintenance. Fan shall be assembled to bulkhead wall with minimal fasteners and the fan shall have quick disconnects for the high voltage and low voltage connections.
- 10. For units utilizing multiple fans in a fan section, a fan curve shall be provided showing the performance of the entire bank of fans at design conditions. In addition, a fan curve shall be provided showing the performance of each individual fan in the bank of fans at design conditions. Also a fan curve shall be provided showing the performance of the bank of fans, if one fan is down. The percent redundancy of the bank of fans with one fan down shall be noted on the fan curve or in the tabulated fan data.

On units supplied with plenum or motorized impeller fans, door guard(s) shall be supplied on the access door(s) to the fan and those downstream access door(s) where unintended access to the plenum or motorized impeller fan could occur. Door guard is intended to deter unauthorized entry and incidental contact with rotating components. Refer to the Product Data section for fans with access door guard(s).

#### **Motorized Impeller Control Panel with Hand-Off-Auto Switch**

The fan shall be provided with a factory installed NEMA 1 or NEMA 3R motorized impeller motor control panel. The control panel provides a common externally accessible disconnect means, motor over current protection for each fan and a terminal block for ease of control wiring. The box shall include:

- 1.Individual motor protection with individual disconnnecting means with lockable feature. Fusable motor protection is not permissable.
- 2. Fused main panel disconnect with lock out tag out capability
- 3.Common control terminal block for common signal wiring. Single 0-10vdc signal used for fan speed control.
- 4.Control panel box shall be UL508a compliant and manufactured by a UL508a approved manufacturer or UL certified during air handler installation.
- 5. Control panel to include hand/off/auto switch for unit startup and commissioning.
- 6. Dial potentiometer to be included to for manual speed control in the 'hand' position.
- 7.Control panel shall be able to operate fans without a BAS signal for purposes of troubleshooting and commissioning

_			
<b>⊢</b> an	1)	etai	IS.
		- I CII	1.7

Unit Size	17FM	Operating RPM	1,918 rpm
Control Signal	8.5 V	Altitude	0.00 ft

Voltage


Operating Airflow6,700 cfmDesign Temp.52.00 FOperating Static3.698 in H2OEfficiency62.27 %

Pressure

Design voltage is less than 10. Ensure the air delivery system can handle being pressurized to the Maximum static pressure detailed in the product data and shown on the fan curve.

## 17" 4.5KW 208-230V 2 Fan Motorized Impeller Array

17" 4.5KW 208-230V 2 Fan Motorized Impeller Array



_	<b>D</b> (	
⊢an	Deta	มเร

Unit Size	17FM	Altitude	0.00 ft
Control Signal Voltage	10.0 V	Design Temp.	52.00 F
Operating Airflow	5.053 cfm	Efficiency	77 60 %

Operating Airflow5,953 cfmEfficiency77.69 %Operating Static2.919 in H2ORedundancy88.85 %

Pressure


Operating RPM 2,262 rpm

One fan down fan curve based on fan isolated via backdraft damper or manual blockoff plate.

Design voltage is less than 10. Ensure the air delivery system can handle being pressurized to the Maximum static pressure detailed in the product data and shown on the fan curve.

### 17" 4.5KW 208-230V 2 Fan Motorized Impeller Array - One Fan Down

17" 4.5KW 208-230V 2 Fan Motorized Impeller Array



_			
⊢ an	1	10tai	ıc
1 011	-	יכומו	15

Unit Size	17FM	Operating RPM	1,918 rpm
Control Signal	8.5 V	Altitude	0.00 ft

Voltage


Operating Airflow3,350 cfmDesign Temp.52.00 FOperating Static3.698 in H2OEfficiency84.25 %

Pressure

Design voltage is less than 10. Ensure the air delivery system can handle being pressurized to the Maximum static pressure detailed in the product data and shown on the fan curve.

# 17" 4.5KW 208-230V 2 Fan Motorized Impeller Array - Single Fan

17" 4.5KW 208-230V 2 Fan Motorized Impeller Array



# 4 SUPPLY FAN (4)MICBINITION (4)MICBINITION (5)MICBINITION (A)MICBINITION (CC) (CC)

DATE 7/10/2024

SOFTWARE MERSON

DRAWING VERSION

Trane

CSIA—SCHEMATIC

UNIT SIZE: 17

UNIT TAG: AHU 1—2

# LEGEND DETAIL 1

	BUILD				PWR	SIGNAL		POWER
POS#	GROUP	DESCRIPTION	PT	LABEL	HR-WIRE	HR-WIRE	XFMR	VA
3	_	Supply Fan Speed Command		MICP1				
3	2	Supply Fan Speed Command (MICP	)AO1	VFD1				
3	2	Supply Fan Speed Command (MICP	<b>A</b> 02	VFD2				
4	3	Supply Fan Speed		SF1				

DRAWN BY SERVICE ACCOUNT	Trane	
DATE 7/10/2024		CSIA-SCHEMATIC
SOFTWARE VERSION		UNIT SIZE: 17
DRAWING VERSION		UNIT TAG: AHU 1-2